

Preliminary Design Review

Presented by: Manhattan 2 Rollable PV Capstone Team




Agenda

- 1. Project Goals
- 2. Concept Development
- 3. Preliminary Concept Design
- 4. Budget and Preliminary Parts List
- 5. Project Risk and Abatement Plan
- 6. Conclusion
- 7. Questions



Project Goals



The Ohio State University

Deliverables


A written report with the following will be provided as the final result:

- Electrical Simulations
 - Multiple panel power combination
 - Effect of lightning strikes and static discharge
- Additional Simulations
 - 30-year simulation detailing effects of weather on soil erosion, wind effects, and heat dissipation
- Technical Drawings
 - Detailed drawings and explanation of method, materials, and equipment needed to install rollable PV cells direct to land

* A small-scale "proof of concept" prototype will also be provided depending on Ohio State's future COVID-19 restrictions *




Past Milestones






Future Goals





Concept Development





Concept Road Map

- Research
 - Meetings with Glenn Weinreb
 - o Individual research
- Group Brainstorming
 - General discussion on needs and requirements
- Attribute Listing
 - Table of essential project components
- Individual Design
 - Each member created a concept design for the module system



Needs Chart

Design Needs	Priority [1(low) - 5(high)]
Improve Electrical Safety	5
Reduce Material Cost	5
Increase Scalability	4
Increase Heat Dissipation	2
System Monitoring	3
Increase Durability (Lifetime)	3
Enterprise Needs	
Reduce Production Cost	5
Reduce Lead Time for Production	1



Attribute Listing

Weather protection	Panel Holds/Attachments	Land Installation Process	Heat Distribution	Power Conversion
Glass Layer above	Staking to ground	Shape Land	Panel Elevation	Power Routing
extreme weather - tarp	Panel Orientation	Wiring	Spacing	Transformer Conversion
waterproof	Electrical Connections	Lay Panels	Material	Power Correction
dust shielding	Panel Clamping	Connect wiring to solar		
		Easy connection between module		




Attribute Listing

Electrical Protection	Communications	Economics	Maintenance	Dropping Weight
	Microcontroller		Day to Day	
Lightning Rods	Placement	Material choice	Cleaning	Different Materials
				Different Way of
Gas Discharge Tubes	User Interface	Labor demands	Anchoring repairs	Laying Down
Material choice to	Monitoring			
reduce discharge	Components	Power costs	Electrical Repairs	
			Weather Damage	


The Ohio State University

Concept A



- 1. Lightning rods every other panel
- 2. Gas discharge tubes for each rollable section
- 3. Microcontrollers for each rollable section and for monitoring power conversion
- 4. Deep anchors into rock layers
- 5. Elevated edges for protection
- 6. Maintenance tunnel for wire routing


Concept B



- 1. Formed soil mounds
- 2. Plastic sheeting to prevent erosion
- 3. Aluminum panel
- 4. Buried Mesh layer
- 5. Lightning rods
- 6. Electrical System
- 7. Panels laid out

The Ohio State University


Concept C



- 1. Screw anchoring system for quick installation
- 2. Electrical Cross-connections to prevent single point failures
- External monitoring system to assist in maintenance plans and diagnostics
- 4. Processors to remove underperforming cells




Concept D



- 1. Rollable Solar Panel
- 2. Rollable Thermal Material
- 3. Lightning Rods
- 4. Supports
- 5. Power and communication bus conduit
- 6. Lightning strike overvoltage protection
- 7. Microcontroller
- 8. Power Combination


The Ohio State University

Concept E



- 1. Flexible, Rollable Panels
- 2. Placed on Pivoting Bases
- 3. Lightning Rods Throughout the Field
- 4. Clear, Protective Film Angled above Panels
- 5. Electrical Components Running through the Ground
- 6. Microcontroller for Subsections
- Control Center for Overall System

Concept F



- 1. Packed soil at 30 degree angles
- 2. Tarp with rolled solar panel attached laid overtop mounds
- 3. Tarp staked down at multiple points over 60 degree portion
- 4. Single mound in front of first row for dust protection
- 5. Gas discharge tubes at the end of each row
- 6. Lightning rods with every module
- 7. Microcontroller for system monitoring
- 8. Motorized brushes to sweep panels

Concept Reference



Topaz Solar Farm [1]

- Individual panels connected together
- Sections are supported by vertical I-beams
- Wiring located on underside of panels

Concept Screening Matrix


Needs	Concept A	Concept B	Concept C	Concept D	Concept E	Concept F	Reference
Electric Safety	+	+	0	+	+	+	0
Material Cost	-	+	-	-	+	+	0
Electric Production	0	0	0	0	+	0	0
Scalability	0	+	0	0	-	+	0
Heat Dissipation	0	-	0	+	-	-	0
System Monitoring	+	+	+	0	0	+	0
Durability	+	-	+	+	0	-	0
Installation Cost	-	+	-	-	+	+	0
Lead Time	-	+	-	0	0	+	0
Ease of Installation	-	+	-	-	-	+	0
Ease of Maintenance	+	+	0	0	0	+	0
Weight of Structure	-	+	-	-	-	+	0
Sum of +'s	4	9	2	3	4	9	0
Sum of 0's	3	1	5	5	4	1	12
Sum of -'s	5	2	5	4	4	2	0
Net Score	-1	7	-3	-1	0	7	0
Rank	5	1	7	5	3	1	3

Concept Scoring Matrix

Needs	Weights	Conc	ept A	Conc	ept B	Conc	ept C	Conc	ept D	Conc	ept E	Conc	ept F
Inceds	weights	Rating	Score										
Scalability	18.0%	4	0.72	5	0.9	4	0.72	4	0.72	4	0.72	5	0.9
Material Cost	14.0%	2	0.28	4	0.56	2	0.28	2	0.28	3	0.42	4	0.56
Installation Cost	14.0%	2	0.28	4	0.56	2	0.28	3	0.42	4	0.56	4	0.56
Ease of Installation	14.0%	2	0.28	5	0.7	2	0.28	2	0.28	2	0.28	5	0.7
Electric Safety	8.0%	5	0.4	4	0.32	3	0.24	4	0.32	3	0.24	4	0.32
Heat Dissipation	8.0%	4	0.32	1	0.08	4	0.32	5	0.4	2	0.16	1	0.08
Durability	8.0%	3	0.24	2	0.16	4	0.32	3	0.24	3	0.24	1	0.08
Weight of System	6.0%	1	0.06	5	0.3	1	0.06	2	0.12	2	0.12	5	0.3
System Monitoring	4.0%	5	0.2	4	0.16	5	0.2	5	0.2	4	0.16	4	0.16
Ease of Maintenance	4.0%	3	0.12	3	0.12	2	0.08	3	0.12	2	0.08	3	0.12
Energy Efficiency	1.0%	1	0.01	2	0.02	3	0.03	3	0.03	5	0.05	1	0.01
Lead Time	1.0%	1	0.01	4	0.04	2	0.02	2	0.02	2	0.02	4	0.04
	100%												
	Net Score	2.	91	3.	88	2.	81	3.	13	3.	03	3.	79
	Rank	4	5		L	(5	3	3	2	1		2



Preliminary Concept Design





Overview

- Installation Method
- Anchoring

Soil

Controllers

Solar Panel

Communication Module


Electrical Protection

Thermal Material

Underground Mesh


Support Brackets

Wire Routing




The Ohio State University

Installation Method / Anchoring






Electrical Protection / Routing





Design Metrics

- Created measurable metrics based on design needs
- Based on current issues within the solar industry and needs with current design



User Need	Specific User Need	Design Requirement	Metric	Range	Goal
Cost	Material Cost	Cost Reduction	USD	5%-25%	15%
	Installation Cost	Cost Reduction	USD	10%-60%	0.3
Scalability	Installation	Installation Time	Months	1-3	3
	Weight of System	Weight Reduction	Pounds	10%-30%	20%
	Ease of Maintenance	Reduction in Labor	Hours	1%-10%	5%
System Performance	System Monitoring	Microcontrollers	Count	1-5	4
	Durability	Similar to Current Lifespan	Years	20 - 30	25
	Heat Dissipation	Temperature of Electronics	Degree Celsius	20-40	30
	Energy Efficiency	Similar to Current Efficiency	% Efficient	15%-23%	18%
Safety	Lightning Protections	Lighning Rods	Count	1-4	1
	Surge Protections	Gas Discharge Tubes	Count	1-5	4



Broader Impacts

- Environmental Impact
 - Reduction in greenhouse gases and air pollution produced by the energy industry
- Industrial Impact
 - Electric Power Industry
 - Electronics Industry
 - Fossil Fuel Industry





Broader Impacts






- Social Impact
 - Reduction of jobs in traditional fuel industries
 - Increase of jobs in manufacturing of solar panels and solar industry
- Political Impact
 - Decrease in tensions between countries due to fossil fuel needs
 - Increase in tensions whose exports involve fossil fuels
 - Improvement in energy production in 3rd world countries



Budget and Preliminary Parts List





Budget & Materials

Total Budget

• \$3,500

Material Groups

- Electrical
- Mechanical
- Installation

Preliminary Parts List						
Electrical Components	Mechanical Components	Installation Equipment				
Microcontrollers	Metal Mesh	Backhoes				
Lightning Rods	Metal Sheeting	Tractors				
Gas Discharge Tubes	Tarps					
Wire Routing	Metal Anchoring Rods					
Transformers	90° Metal Bracketing					
Capacitor Banks	Thermal Material					
DC to AC converters	Plywood					
	Fasteners					
	Stakes					



Project Risk and Abatement Plan





Temperature

- Day temperatures exceeding 110F
- Night temperatures below 0F
- Possible material degradation due to thermal cycling and solar radiation
 - Plan: Careful selection of materials
- Possible localized heat island effect
 - Plan: Account for effect in simulations



Dust, Soil, and Erosion

- Dust covering panels reduces efficiency
 Plan: Incorporate a dust removal system
- Incompatibility of anchoring method with soil composition
 - Plan: Test the anchoring method with the various soil compositions found in the American Southwest.
- Erosion destroys the sloped land dunes
 - Plan: Plastic sheeting laid to reduce erosion and exposure to weather


The Ohio State University

Electrical Malfunction

- Destruction of electrical components from lightning
 - Installation lightning rods to ground lightning strikes
- Electrostatic discharge shorting electrical components
 - Installation of gas discharge tubes to each panel section
- Panels operating outside of expected parameters
 - Microcontrollers monitoring panel and system outputs




Conclusion



The Ohio State University


Conclusion

- The team considered various attributes needed within a final design
- Each member created their own individual concept
- These concepts were all considered, and a preliminary design concept was created
- A preliminary budget and parts were created based on this design
- Various risks and abatement plans to the project were considered as well





Questions?





Sources

[1] "The world's biggest solar power plants," Power-Technology.com.

https://www.power-technology.com/features/the-worlds-biggest-solar-power-plants/attachment/1-image-topaz-sol ar-farm/ (accessed 15-Nov-2020).